Marcegaglia SM8 2.50 × 1.14 m vs Layher Allround LW 2.57 × 1.09 m

On a straight façade, Layher Allround LW leads at this module on speed, weight and cost.

- Same structure: identical piece, node and wedge counts — the difference comes only from unit weights and time standards.
- Layher Allround LW is faster: 33% fewer man-hours per m² (time standard status: provisional).
- Layher Allround LW is lighter: 10% less kg per m² — 100% of its weight is estimated.
- Layher Allround LW is cheaper: 11% per m² (1-month rental + labour + transport).

KEY FIGURES — STRAIGHT FAÇADE, 10 BAYS × 4 LIFTS (8 M), TIED

Man-hours per m² lower is better



kg per m² lower is better



EUR per m² lower is better



Module	SM8	Layher	Δ
Bay × width (m)	2.50 × 1.14	2.57 × 1.09	
Deck area per bay (m²)	2.85	2.80	-1.7%
Decks across × width	3 × 330 mm (87%)	3 × 320 mm (88%)	
Clear platform width (m)	1.14	1.09	-4.4%
Load class at this bay	4	5 (est.)	
Node / wedge	octagonal plate, manual wedge	rosette, AutoLock wedge	

Façade	SM8	Layher	Δ Layher
Face area (m²)	200.0	205.6	
Pieces / nodes / wedges	649 / 286 / 694	649 / 286 / 694	identical
Weight (t)	6.53	6.06 (100% est.)	-7.2%
kg per m²	32.7	29.5	-9.7%
Erection man-hours (crew 5)	14.6	10.0	-31.6%
Elapsed (min)	175	120	-31.6%
m² per man-hour	13.7	20.6	+50.2%
Extra bay, all lifts: kg	676	643	-4.9%
Extra bay, all lifts: man-h	1.46	1.08	-26.1%
Unsecured-connection exposure (man-h)	1.38	0.94	-31.6%
Cost per m² (EUR)	11.83	10.49	-11.3%

WHERE THE WEIGHT SITS — UNIT WEIGHTS (KG)

Component	SM8 code	kg	Layher code	kg	Δ
Standard 2.0 m	SM8-STD-200	9.86	LAY-STD-200	9.20	-6.7%
Ledger (bay)	SM8-LED-250	10.00	LAY-LED-257	8.80	-12.0%
Ledger / transom (width)	SM8-LED-114	4.80	LAY-LED-109	4.60	-4.2%
Steel deck (bay)	SM8-DECK-250	14.38	LAY-DECK-257	15.00	+4.3%
Diagonal (bay)	SM8-DIA-250	7.82	LAY-DIA-257	8.60	+10.0%
Toe board (bay)	SM8-TOE-250	8.20	LAY-TOE-257	6.40	-22.0%
Hatch deck	SM8-HATCH-250	32.38	LAY-HATCH-257	25.00	-22.8%

Highlighted = **estimate** (not verified). Δ is Layher vs SM8; green = better.

To confirm before deciding

1. Load the current Layher Allround LW price list: 100% of its weight is estimated.
2. Re-run the reference tower to the Annex A protocol (3 runs per system, phase timestamps, same crew) to confirm the time difference and where it comes from.
3. Confirm Layher Allround LW load class 5 at 2.57 m bays against the approval.

Scope

Module level only. Hull fit (infills on curved shell and flare) is assessed per area: Layher's finer grid wins on moderate curvature; SM8's longer brackets help on strong flare.

SM8: catalogue 2026.11-r1 (108fe70003503980), time std PROV-2026.11-r1 [provisional].
Layher: catalogue 2026.11-r1 (618505b7d855ade4), time std PROV-2026.11-r1 [provisional].
Cost: 1-month rental + labour (erection + dismantling) + transport, settings in data/settings.yaml.

Disclaimer. Planning and comparison aid only — not a structural design or certification tool. Every scaffold must be designed and approved per the manufacturer's approval (Layher DIBt approvals, SM8 ministerial authorisation), EN 12810 / EN 12811 and Romanian OSH rules, and inspected by a competent person before use.